

**SECTION 32 14 13  
INTERLOCKING CONCRETE PAVEMENT OVERLAY  
(1995 MasterFormat Section 02780)**

*Note: This guide specification for Canada is for the construction of a new or rehabilitative overlay of concrete pavers and bedding sand over an existing asphalt, concrete, or aggregate base. Applications include pedestrian and vehicular areas. The text must be edited to suit specific project requirements. This Section includes the term "Architect." Edit this term as necessary to identify the design professional in the General Conditions of the Contract.*

**PART 1 GENERAL**

**1.01 SUMMARY**

- A. Section Includes
  - 1. Concrete paver units.
  - 2. Bedding and joint sand.
  - 3. Geotextiles.
  - 4. Edge restraints.
  - 5. [Cleaners and Sealers]
- B. Related Sections
  - 1. Section: [ ]- Curbs and Drains.
  - 2. Section: [ ]- Concrete Base.
  - 3. Section: [ ]- Pavements, Asphalt and Concrete.
  - 4. Section: [ ]- Geotextiles.

*Note: Pavements subject to vehicles should be designed in consultation with a qualified civil engineer, in accordance with established pavement design procedures, ICPI Lockpave software, and in accordance with the ICPI Tech Spec technical bulletins. Use the current year reference.*

**1.02 REFERENCES**

- A. Canadian Standards Association (CSA)
  - 1. CSA-A231.2, Precast Concrete Pavers.
  - 2. CSA-A23.2A, Sieve Analysis of Fine and Coarse Aggregates.
  - 3. CSA-A23.1-FA1, Concrete Materials and Methods of Concrete Construction.
  - 4. CSA-A179, Mortar and Grout for Unit Masonry.
- B. American Society of Testing and Materials (ASTM):
  - 1. C 979, Standard Specification for Pigments for Integrally Coloured Concrete.
- B. Interlocking Concrete Pavement Institute (ICPI)
  - 1. ICPI Tech Spec Technical Bulletins

**1.03 SUBMITTALS**

- A. In accordance with Conditions of the Contract and Division 1 Submittal Procedures Section.
- B. Manufacturer's drawings and details: Indicate perimeter conditions, relationship to adjoining materials and assemblies, [expansion and control joints,] concrete paver [layout,] [patterns,] [colour arrangement,] installation [and setting] details.
- C. Sieve analysis per CSA A23.2A for grading of bedding and joint sand.
- D. [Bedding sand durability test results.]
- E. Concrete pavers:
  - 1. [Four] representative full-size samples of each paver type, thickness, colour, finish that indicate the range of colour variation and texture expected in the finished installation. Colour(s) selected by [Architect] [Engineer] [Landscape Architect] [Owner] from manufacturer's available colours.
  - 2. Accepted samples become the standard of acceptance for the work.
  - 3. Test results from an independent testing laboratory for compliance of paving unit requirements to CSA A231.2.
  - 4. Manufacturer's certification of concrete pavers by ICPI as having met applicable CSA and ASTM standards.

5. Manufacturer's catalog product data, installation instructions, and material safety data sheets for the safe handling of the specified materials and products.
- F. Paver Installation Subcontractor:
1. A copy of Subcontractor's current certificate from the Interlocking Concrete Pavement Institute Concrete Paver Installer Certification program.
  2. Job references from projects of a similar size and complexity. Provide Owner/Client/General Contractor names, postal address, phone, fax, and email address.
- 1.04 QUALITY ASSURANCE
- A. Paving Subcontractor Qualifications:
1. Utilize an installer having successfully completed concrete paver installation similar in design, material, and extent indicated on this project.
  2. Utilize an installer holding a current certificate from the Interlocking Concrete Pavement Institute Concrete Paver Installer Certification program.
- B. Regulatory Requirements and Approvals: [Specify applicable licensing, bonding or other requirements of regulatory agencies].
- C. Mock-Ups:
1. Install a 2 x 2 m paver area.
  2. Use this area to determine surcharge of the bedding sand layer, joint sizes, lines, laying pattern(s), colour(s), and texture of the job.
  3. This area will be used as the standard by which the work will be judged.
  4. Subject to acceptance by owner, mock-up may be retained as part of finished work.
  6. If mock-up is not retained, remove and properly dispose of mock-up.
- 1.05 DELIVERY, STORAGE & HANDLING
- A. General: Comply with Division 1 Product Requirement Section.
- B. Comply with manufacturer's ordering instructions and lead-time requirements to avoid construction delays.
- C. Delivery: Deliver materials in manufacturer's original, unopened, undamaged containers packaging with identification labels intact.
1. Coordinate delivery and paving schedule to minimize interference with normal use of buildings adjacent to paving.
  2. Deliver concrete pavers to the site in steel banded, plastic banded or plastic wrapped packaging capable of transfer by fork lift or clamp lift.
  3. Unload pavers at job site in such a manner that no damage occurs to the product.
- D. Storage and Protection: Store materials protected such that they are kept free from mud, dirt, and other foreign materials. [Store concrete paver cleaners and sealers per manufacturer's instructions.]
1. Cover bedding sand and joint sand with waterproof covering if needed to prevent exposure to rainfall or removal by wind. Secure the covering in place.
- 1.06 PROJECT/SITE CONDITIONS
- A. Environmental Requirements:
1. Do not install sand or pavers during heavy rain or snowfall.
  2. Do not install sand and pavers over frozen aggregate base materials.
  3. Do not install frozen sand or saturated sand.
  4. Do not install concrete pavers on frozen or saturated sand.
- 1.07 MAINTENANCE
- A. Extra Materials: Provide [Specify area] [Specify percentage.] additional material for use by owner for maintenance and repair.
- B. Pavers shall be from the same production run as installed materials.

## PART 2 PRODUCTS

### 2.01 CONCRETE PAVERS

*Note: Concrete pavers may have spacer bars on each unit. They are highly recommended for mechanically installed pavers. Manually installed pavers may be installed with or without spacer bars.*

- A. Manufacturer: [Specify ICPI member manufacturer name.].
  - 1. Contact: [Specify ICPI member manufacturer contact information.].
- B. Concrete Pavers:
  - 1. Paver Type: [Specify name of product group, family, series, etc.].
    - a. Material Standard: Comply with material standards in CSA A231.2.
    - b. Colour [and finish]: [Specify colour.] [Specify finish].
    - c. Colour Pigment Material Standard: Comply with ASTM C 979.
    - d. Size: [Specify mm] x [Specify mm] x [Specify mm] thick.
    - e. Average Cube Compressive Strength: 50 MPa with no individual unit under 45 MPa.
    - f. Freeze/Thaw Deicing Salt Resistance: No greater loss of 200 g/m<sup>2</sup> of surface area after 200 freeze-thaw cycles or no great loss of 500 g/m<sup>2</sup> of surface area after 50 cycles while immersed in a 3% saline solution. Freeze-thaw testing requirements shall be waived for applications not exposed to freezing conditions.

### 2.02 PRODUCT SUBSTITUTIONS

- A. Substitutions: No substitutions permitted.

### 2.03 BEDDING AND JOINT SAND

- A. Provide bedding and joint sand as follows:
  - 1. Washed, clean, non-plastic, free from deleterious or foreign matter, symmetrically shaped, natural or manufactured from crushed rock.
  - 2. Do not use limestone screenings, stone dust, or sand for the bedding sand material that do not conform to the grading requirements of CSA A23 A23.1-FA1.
  - 3. Do not use mason sand or sand conforming to CSA-A179 for the bedding sand.

*Note: Bedding sand durability is important for crosswalks and other vehicular pavements exposed to high traffic. The engineer/architect is advised to evaluate the hardness of bedding sand with the following test method when the pavers and sand will be placed over concrete, or asphalt, and subject to major thoroughfare traffic (over 1.5 million ESALs): One (1) 1.4 kg sample of bedding sand can be randomly sampled from the sand source. The sample is dried for 24 hours at 115° to 121° C. Obtain three (3) sub-samples each weighing 0.2 kg by passing the main sample several times through a riffle box. Carry out a sieve analysis test on each sub-sample according to CSA A23.2A. Re-mix each sub-sample and place in a nominal quart/liter capacity porcelain jar with two (2) 25 mm diameter steel ball bearings weighing 75 ±5 grams each. Rotate each jar at 50 rpm for six (6) hours. Repeat the sieve analysis. Record the individual and average sieve analysis. For each sample tested, the maximum increase in the percentages passing each sieve and the maximum individual percent passing should be as follows:*

Sieve Size	Max. Increase	Maximum Passing
0.075 mm	2%	2%
0.150 mm	5%	15%
0.300 mm	5%	35%

- 4. Where concrete pavers are subject to vehicular traffic, utilize sands that are as hard as practically available.
- 5. Sieved per CSA-A23.2A and conform to the grading requirements of CSA-A23.1-FA1 with modifications in Table 1 below:

Table 1  
Grading Requirements for Bedding Sand  
CSA A23.1-FA1

Sieve Size	Percent Passing
10 mm	100
5 mm	95 to 100
2.5 mm	80 to 100
1.25 mm	50 to 90
0.630 mm	25 to 65
0.315 mm	10 to 35
0.160 mm	2 to 10
0.075 mm	0 to 1

6. Do not use limestone screenings or stone dust or sand for the bedding material that does not conform to the grading requirements of CSA A23.1-FA1 in Table 1.

*Note: Coarser sand than that specified in Table 2 below may be used for joint sand including A23.1 material as shown in Table 1. Use material where the largest sieve size easily enters the smallest joints. For example, if the smallest paver joints are 2 mm wide, use sand 2 mm and smaller in particle size. If A23.1 sand is used for joint sand, extra effort may be required in sweeping material and compacting the pavers in order to completely fill the joints.*

- B. Joint Sand Material Requirements: Conform to the grading requirements of CSA A179 as shown with modifications in Table 2 below:

Table 2  
CSA A179 Grading Requirements for Joint Sand

Sieve Size	Percent Passing
5 mm	100
2.5 mm	90 to 100
1.25 mm	85 to 100
0.630 mm	65 to 95
0.315 mm	15 to 80
0.160 mm	0 to 35
0.075 mm	0 to 1

*Note: Specify specific components of a system, manufactured unit or type of equipment. See ICPI Tech Spec 3, Edge Restraints for Interlocking Concrete Pavements for guidance on selection and design of edge restraints.*

#### 2.04 EDGE RESTRAINTS

- A. Provide edge restraints installed around the perimeter of all interlocking concrete paving unit areas as follows:
1. Manufacturer: [Specify manufacturer.].
  2. Material: [Plastic] [Concrete] [Aluminum] [Steel] [Pre-cast concrete] [Cut stone] [Concrete].
  3. Material Standard: [Specify material standard.].

#### 2.05 ACCESSORIES

- A. Provide accessory materials as follows:
1. Geotextile Fabric:
    - a. Material Type and Description: [Specify material type and description.].
    - b. Material Standard: [Specify material standard.].
    - c. Manufacturer: [Acceptable to concrete paver manufacturer] [Specify manufacturer.].

*Note: Delete article below if cleaners, sealers, and/or joint sand stabilizers are not specified.*

2. [Cleaners] [Sealers] [Joint sand stabilizers]
  - a. Material Type and Description: [Specify material type and description].
  - b. Material Standard: [Specify material standard.].
  - c. Manufacturer: [Specify manufacturer.].

### **PART 3 EXECUTION**

#### **3.01 ACCEPTABLE INSTALLERS**

- A. [Specify acceptable paving subcontractors.].

*Note: The elevations and surface tolerance of the base determine the final surface elevations of concrete pavers. The paver installation contractor cannot correct deficiencies in the base surface with additional bedding sand or by other means. Therefore, the surface elevations of the base should be checked and accepted by the General Contractor or designated party, with written certification to the paving subcontractor, prior to placing bedding sand and concrete pavers.*

#### **3.02 EXAMINATION**

- A. Acceptance of Site Verification of Conditions:
  1. General Contractor shall inspect, accept and certify in writing to the paver installation subcontractor that site conditions meet specifications for the following items prior to installation of interlocking concrete pavers.
    - a. Verify that subgrade preparation, compacted density and elevations conform to specified requirements.
    - b. Verify that geotextiles, if applicable, have been placed according to drawings and specifications.
    - c. Verify that [Aggregate] [Cement-treated] [Asphalt-treated] [Concrete] [Asphalt] base materials, thickness, [compacted density], surface tolerances and elevations conform to specified requirements.
    - d. Provide written density test results for soil subgrade, [aggregate] [cement-treated][asphalt-treated][asphalt] base materials to the Owner, General Contractor and paver installation subcontractor.
    - e. Verify location, type, and elevations of edge restraints, [concrete collars around] utility structures, and drainage holes and inlets.
  2. Do not proceed with installation of bedding sand and interlocking concrete pavers until [subgrade soil and] base conditions are corrected by the General Contractor or designated subcontractor.

#### **3.03 PREPARATION**

- A. Verify base is clean and dry, certified by General Contractor as meeting material, installation and grade specifications.
- B. Verify that base [and geotextile] is ready to support sand, [edge restraints,] and, pavers and imposed loads.
- C. Edge Restraint Preparation:
  1. Install edge restraints per the drawings [and manufacturer's recommendations] [at the indicated elevations].

*Note: Retain the following two subparagraphs if specifying edge restraints that are staked into the base with spikes.*

2. Mount directly to finished base. Do not install on bedding sand.
3. The minimum distance from the outside edge of the base to the spikes shall be equal to the thickness of the base.

## 3.04 INSTALLATION

- A. Spread bedding sand evenly over the base course and screed to a nominal 1 in. (25 mm) thickness. Spread bedding sand evenly over the base course and screed rails, using the rails and/or edge restraints to produce a nominal 1 in. (25 mm) thickness, allowing for specified variation in the base surface.
1. Do not disturb screeded sand.
  2. Screeded area shall not substantially exceed that which is covered by pavers in one day.
  3. Do not use bedding sand to fill depressions in the base surface.

*Note: When initially placed on the bedding sand, manually installed pavers often touch each other, or their spacer bars if present. Joint widths and lines (bond lines) are straightened and aligned to specifications with rubber hammers and pry bars as paving proceeds.*

- B. Lay pavers in pattern(s) shown on drawings. Place units hand tight without using hammers. Make horizontal adjustments to placement of laid pavers with rubber hammers as required.

Note: Contact manufacturer of interlocking concrete paver units for recommended joint widths.

- C. Provide joints between pavers between [2 and 5 mm] wide. No more than 5% of the joints shall exceed [6 mm] wide to achieve straight bond lines.
- D. Joint (bond) lines shall not deviate more than  $\pm 15$  mm over 15 m from string lines.
- E. Fill gaps at the edges of the paved area with cut pavers or edge units.
- F. Cut pavers to be placed along the edge with a [double blade paver splitter or] masonry saw.

*Note. Specify requirements for edge treatment in paragraph below.*

- G. [Adjust bond pattern at pavement edges such that cutting of edge pavers is minimized. All cut pavers exposed to vehicular tires shall be no smaller than one-third of a whole paver.] [Cut pavers at edges as indicated on the drawings.]
- H. Keep skid steer and forklift equipment off newly laid pavers that have not received initial compaction and joint sand.
- I. Use a low-amplitude plate compactor capable of at least minimum of 18 kN at a frequency of 75 to 100 Hz to vibrate the pavers into the sand. Remove any cracked or damaged pavers and replace with new units.
- J. Simultaneously spread, sweep and compact dry joint sand into joints continuously until full. This will require at least 4 to 6 passes with a plate compactor. Do not compact within 2 m of unrestrained edges of paving units.
- K. All work within 2 m of the laying face must shall be left fully compacted with sand-filled joints at the end of each day or compacted upon acceptance of the work. Cover the laying face or any incomplete areas with plastic sheets overnight if not closed with cut and compacted pavers with joint sand to prevent exposed bedding sand from becoming saturated from rainfall.
- L. Remove excess sand from surface when installation is complete.

*Note: Excess joint sand can remain on surface of pavers to aid in protecting their surface especially when additional construction occurs after their installation. If this is the case, delete the article above and use the article below. Designate person responsible for directing timing of removal of excess joint sand.*

- M. Allow excess joint sand to remain on surface to protect pavers from damage from other trades. Remove excess sand when directed by [Architect].
- N. Surface shall be broom clean after removal of excess joint sand.

## 3.05 FIELD QUALITY CONTROL

*Note: Surface tolerances on flat slopes should be measured with a rigid straightedge. Tolerances on complex contoured slopes should be measured with a flexible straightedge capable of conforming to the complex curves on the pavement surface.*

- A. The final surface tolerance from grade elevations shall not deviate more than  $\pm 3/8$  in. ( $\pm 10$  mm) under a 3 m straightedge.
- B. Check final surface elevations for conformance to drawings.

*Note: For installations on a compacted aggregate base and soil subgrade, the top surface of the pavers may be 3 to 6 mm above the final elevations after compaction. This helps compensate for possible minor settling normal to pavements.*

- C. The surface elevation of pavers shall be 3 to 6 mm above adjacent drainage inlets, concrete collars or channels.
- D. Lippage: No greater than 3 mm difference in height between adjacent pavers.

*Note: Cleaning and sealing may be required for some applications. See ICPI Tech Spec 5, Cleaning and Sealing Interlocking Concrete Pavements for guidance on when to clean and seal the paver surface, and when to stabilize joint sand. Delete article below if cleaners, sealers, and or joint sand stabilizers are not applied.*

3.06 [CLEANING] [SEALING] [JOINT SAND STABILIZATION]

- A. [Clean] [Seal] [Apply joint sand stabilization materials between] concrete pavers in accordance with the manufacturer's written recommendations.

3.07 PROTECTION

- A. After work in this section is complete, the General Contractor shall be responsible for protecting work from damage due to subsequent construction activity on the site.

END OF SECTION